



Your Single Source For Broadcast Solutions

Structural Evaluation of Pipe Leg Tower and the Engineering and Execution of Controlled Demolition of Guyed Towers

Presented By: Shawn Knotts
Western Region Account Manager
Electronics Research, Inc.



Your Single Source For Broadcast Solutions

ANSI/TIA-1019-A-2011:

ANSI/TIA-1019-A-2011
APPROVED: Aug. 29, 2011

ANSI/TIA STANDARD

Standard for Installation, Alteration and
Maintenance of Antenna Supporting Structures and
Antennas

TIA-1019-A

Aug. 29, 2011

TELECOMMUNICATIONS
INDUSTRY ASSOCIATION
TR14.7 Sub-committee

tiaonline.org

Approved August 2011



TIA-1019-A Minimum Strength Req's:

Loads to be Considered:

1) Operational Loads:

- *Rigging System Loads During Construction

- *Uniform 30MPH Wind

2) Non-Operational Loads:

- *Rigging System Loads Applied While Construction is NOT in Progress (i.e. Overnight, Down Days, etc.)

- *Reduced Wind Load Ranging Between 50-100% of Design Wind Speed (Not Exceeding 90MPH)



****Non-Operational Loads Generally Govern***



Minimum Strength Conditions:

If a tower cannot be verified with a reasonable degree of engineering to meet minimum strength conditions of TIA 1019-A, personnel should **NOT** be on or around the tower during construction.

This situation leaves very limited options!




Subject Project:

- 490' Guyed Tower Located in Congested Residential Area (6 Guy Levels/50% Guy Radius)
- Local Crew Noted Severe Corrosion While Preparing to Rig Tower for an FM Install
- ERI Conducted Initial Climbing Inspection and Condition Assessment
- Performed Deterioration Analysis of Tower in Accordance with TIA-1019-A
- Prepared Engineered Rigging Plan to Safely Deconstruct Mast ~ Controlled Drop
- Executed Plan With Onsite Engineering Supervision



Congested Residential Area:

Your Single Source For Broadcast Solutions





Homes
Within 200'

Power Lines
Within 150'



Inspection & Condition Assessment:

Your Single Source For Broadcast Solutions





Inspection Tools:

*Ultrasonic (UT) / FO Borescope:




*3 lb Sledge:






Deterioration Tower Analysis:

*Reduced Buckling Strength Calculated




Strength Reduced by Over 50%!!!



*Multiple Analyses Were Conducted to Determine Method for Dismantling

- First Choice ~ Light-Weight Gin Pole





Dismantling Considerations (TIA-1019-A):


- Structure must be capable of safely resisting construction loads imposed by Rigging System during de-stacking operations (i.e. Gin Pole, Slings, Blocks, etc.)
- Rigged tower must be capable of withstanding minimum wind forces of 45 mph to 60 mph during non-operational times depending upon duration of de-construction period
 - MAJOR LOAD TO CONSIDER ~ Gin Pole



Controlled Demolition Selected:

Structure Could **NOT** Withstand the Minimum Construction Loads for Conventional De-Stack

Your Single Source For Broadcast Solutions




inxTower	Job	#30505 * ASRN 1050600	Page	1 of 14
Electronics Research, Inc. 7777 Gardner Road Chandler, IN 47610 Phone: (812) 925-6000 FAX: (812) 925-4030	Project	Prichard, AL (Mobile County)	Date	10:05:33 04/06/13
	Client	Clear Channel	Designed by	James Ruedlinger

Leg Interaction Design Data (Compression)									
Section No.	Elevation	Size	Ratio $\frac{P}{F_c}$	Ratio $\frac{M_x}{F_c S_x}$	Ratio $\frac{M_y}{F_c S_y}$	Comb. Stress Ratio	Allow. Stress Ratio	Criteria	
T1	489 - 449	PIPE 2 X-STR	0.375	0.000	0.000	0.375	1.000	HI-3	✓
T2	449 - 449	PIPE 2 X-STR	0.509	0.000	0.000	0.509	1.000	HI-3	✓
T3	449 - 429	PIPE 2 X-STR	0.519	0.000	0.000	0.519	1.000	HI-3	✓
T4	429 - 409	PIPE 2 X-STR	0.484	0.000	0.000	0.484	1.000	HI-3	✓
T5	409 - 389	PIPE 2 X-STR	0.521	0.000	0.000	0.521	1.000	HI-3	✓
T6	389 - 369	PIPE 2 X-STR	0.551	0.000	0.000	0.551	1.000	HI-3	✓
T7	369 - 349	PIPE 2 X-STR	0.640	0.000	0.000	0.640	1.000	HI-3	✓
T8	349 - 329	PIPE 2 X-STR	0.639	0.000	0.000	0.639	1.000	HI-3	✓
T9	329 - 309	PIPE 2 X-STR	1.328	0.000	0.000	1.328	1.000	HI-3	✗
T10	309 - 289	PIPE 2 X-STR	0.690	0.000	0.000	0.690	1.000	HI-3	✓
T11	289 - 269	PIPE 2 X-STR	0.677	0.000	0.000	0.677	1.000	HI-3	✓
T12	269 - 249	PIPE 2 X-STR	0.678	0.000	0.000	0.678	1.000	HI-3	✓
T13	249 - 229	PIPE 2.5 STD	0.601	0.000	0.000	0.601	1.000	HI-3	✓
T14	229 - 209	PIPE 2.5 STD	0.616	0.000	0.000	0.616	1.000	HI-3	✓
T15	209 - 189	PIPE 2.5 STD	0.580	0.000	0.000	0.580	1.000	HI-3	✓
T16	189 - 169	PIPE 2.5 STD	0.581	0.000	0.000	0.581	1.000	HI-3	✓
T17	169 - 149	PIPE 2.5 STD	0.665	0.000	0.000	0.665	1.000	HI-3	✓
T18	149 - 129	PIPE 2.5 STD	0.676	0.000	0.000	0.676	1.000	HI-3	✓
T19	129 - 109	PIPE 2.5 STD	0.650	0.000	0.000	0.650	1.000	HI-3	✓
T20	109 - 89	PIPE 2.5 STD	0.651	0.000	0.000	0.651	1.000	HI-3	✓
T21	89 - 69	PIPE 2.5 STD	0.723	0.000	0.000	0.723	1.000	HI-3	✓
T22	69 - 49	PIPE 2.5 STD	0.739	0.000	0.000	0.739	1.000	HI-3	✓
T23	49 - 29	PIPE 2.5 STD	0.693	0.000	0.000	0.693	1.000	HI-3	✓
T24	29 - 9	PIPE 2.5 STD	0.701	0.000	0.000	0.701	1.000	HI-3	✓
T25	9 - 8.1146	PIPE 2.5 STD	0.625	0.329	0.000	0.954	1.000	HI-3	✓
T26	8.1146 - 6.5729	PIPE 2.5 STD	0.638	0.064	0.000	0.700	1.000	HI-3	✓
T27	6.5729 - 5.0312	PIPE 2.5 STD	0.623	0.091	0.000	0.713	1.000	HI-3	✓
T28	5.0312 - 4	PIPE 2.5 STD	0.624	0.124	0.000	0.748	1.000	HI-3	✓





Your Single Source For Broadcast Solutions

Due to Adjacent Homes, Roads, and Electrical Lines; **Tower Had to Fall Within 150' Radius**



WARNING: Do Not Try This At Home!


Location of Most Severe Corrosion
Engineered to be First Yield Point
*Direct Fall of Top 180'





Your Single Source For Broadcast Solutions


Relaxation & Removal of Pre-Determined Guy Cables in a Sequential Order Based Upon Results of Dismantle Analysis





Your Single Source For Broadcast Solutions

Certain Guy Cables Were Disconnected From Anchors While Others Remained Intact Until The Critical Failure Point Was Reached





Initial Fall Sequence:

Your Single Source For Broadcast Solutions



Matched Analysis Results



Your Single Source For Broadcast Solutions

Secondary Collapse Mode:



Difficult To Predict!
Important to Control Initial Descent



Your Single Source For Broadcast Solutions

RESULTS:

*Tower Collapse Directed Towards SW Guy Path



*Fall Radius Limited to ~125'





Video Footage:

Your Single Source For Broadcast Solutions






Special Concerns With Pipe/Tubing:

- Galvanizing:
 - If Pipe is NOT Properly and Uniformly Galvanized, Dramatic Loss of Material Can Occur in a Relatively Short Period Especially in Highly Corrosive Environments
 - Post-Galvanizing Welding Can Damage Internal Zinc Deposits at and Around Welding Area
- Adequate Ventilation/Drainage Holes:
 - Needed to Prevent Excessive Condensation
 - Allows Direct Drainage for Any Moisture Accumulation
- Thin Walled Sections:
 - Become Compromised With Relatively Small Amounts of Material Loss
 - Early Detection is Critical



Galvanizing Process:

**Adequate Flow and Drainage is Crucial in Uniform Coatings*





Galvanizing Issues:

Your Single Source For Broadcast Solutions

*Recessed Design ~ Good Drainage



*Butt Design ~ Poor Drainage



*Pickling Acid Does Not Fully Drain Which Can Result in Poorly Coated Areas



Your Single Source For Broadcast Solutions

Galvanizing Issues:



Galvanizing **NOT** Uniformly Deposited on Internal Portions of Pipe



Adequate Ventilation/Drainage Holes:

*Ventilation ~ Ensure Pipe's Interior Environment Adjusts Quickly With External Changes in Temperature, Relative Humidity, and Atmospheric Pressure to Prevent Excessive Condensation

*Drainage ~ Ensure Any Accumulated Moisture May Easily Flow Out of Pipe

"Weep Hole"





Your Single Source For Broadcast Solutions

Adequate Ventilation/Drainage Holes:

*Freeze/Thaw Damage





Thin Walled Sections:

*Relatively Small Amounts of Material Loss Can Be Critical to Member's Load Carrying Capability As Compared to Solid Steel Sections





Aging Broadcast Infrastructure:

- Thousands of Pipe/Tube Structures Well Over 20 Years Old Currently In Service
- Ongoing Maintenance Inspections By Qualified Personnel Are Critical To Extending Serviceable Life As Well As Determining When To Safely Decommission Tower
 - Guyed Towers ~ Conduct Thorough Inspection At Least Every 3 Years
 - Self Support Towers ~ Conduct Thorough Inspection At Least Every 5 Years
 - If Site Specific Issues Exist (Such as Corrosion), Inspection Frequency Should Be Increased



Your Single Source For Broadcast Solutions

Bonus Footage





Questions?

Your Single Source For Broadcast Solutions

